



Department of Finance and Purchasing

ADDENDUM #1
APRIL 30, 2015
FIRESTATION #1 APPARATUS BAY FLOOR RECOATING

In accordance with the pre-bid meeting held April 28, 2015, the information regarding the installation of the Portage Fire Department Logo is attached.

Bids remain due by 3:00 p.m., Thursday, May 14, 2015.

All other remaining terms and conditions are unchanged. Questions regarding the scope of work to be accomplished may be directed to Assistant Fire Chief Stacy French at (269) 329-4482. Questions pertaining to the selection process, insurance requirements or other procedural requirements should be directed to Judy Johnson, Purchasing Manager at (269) 324-9284.



DATE: 04/30/15

PREPARED BY: Mike Havers

Surface Preparation

Decorative Logo Install

Previously coated concrete floor.

AREAS TO BE COATED	COAT	Mechanicall abrade, this step will have already been completed from the primary install related to the base contract.			VOLUME SOLIDS	WET MIL THICKNESS		DRY MIL THICKNESS		OVERCOAT TIME @ 77° F and 50% RH	NOTES
		DESCRIPTION	PRODUCT NUMBER	COLOR		MIN	MAX	MIN	MAX		
GP3579 Primer	1	100% solids epoxy	GP3579	Clear	100%	8.0	8.0	8.0	8.0	24 hrs	Refer to product data sheet for application information.
GP3745 Clear Base Coat	2nd	100% solids epoxy	GP3745	Clear	100%	12.0	12.0	12.0	12.0	24hrs	Refer to product data sheet for application information.
Embed/Place Logo											This is to be placed in the wet basecoat of GP3745
GP3745 Clear Saturant Coat	3rd	100% solids epoxy	GP3745	Clear	100%	16.0	16.0	16.0	16.0	24hrs	Refer to product data sheet for application information.
GP3745 Clear Grout Coat	4th	100% solids epoxy	GP3745	Clear	100%	20.0	20.0	20.0	20.0	24 hrs	Refer to product data sheet for application information.

All overcoat times are temperature and humidity dependent!